



Supplemental Plan Check List for Prestress Concrete (2023 LABC)

Plan Check / PCIS App #: _____

Job Address: _____

P.C. Engineer: _____ Phone: _____
(E-mail: first name.last name@lacity.org)

Supervisor Name: _____ Phone: _____

Your feedback is important; please visit our website to complete a Custom Survey at
www.ladbs.org/LADBSWeb/custom-survey.jsf.

If you have any questions or need clarification on any plan check matters, please contact your plan check engineer and/or his or her supervisor.

For instruction and other information, read the attached master plan check list.

Reference code is Building Code Requirements for Structural Concrete (ACI 318-19) and Commentary unless otherwise noted in plan check list.

Obtain the following Information Bulletins, Affidavits or forms from our web site (www.ladbs.org)

A. PLAN DETAILS

1. Provide 1-1/2 in. minimum cover for exterior span, and 3/4 in. minimum cover for interior span of the P/T slab for a 2-hour rating. (LABC 721.1, Table 721.1(1))
2. Provide schedule showing sequence of construction to insure free movement of prestressed elements before connecting into rigid elements. Specify number of elapsed days after pre-stressing prior to connection to rigid elements. (ACI 318-19 Sec 25.9.1.5)
3. Provide complete details of end anchorage and couplers including an approved anchor system with a L. A. Research Report.
4. Provide reinforcement in tendon anchorage zones; local and general zones - to resist bearing, bursting, splitting and spalling forces. (ACI 318-19 Sec 25.9)
5. Provide complete details of tendon layout. Profiles shall be exactly defined by providing dimensions at the high, low and at least one intermediate point. Show all tendon elongation and identify pulled ends and dead ends. Detail tendon placement around openings in slab. Call out tendon size and spacing in lieu of specifying design force.
6. For prestressed slabs with uniformly distributed loads, maximum spacing s of tendons or groups of tendons in at least one direction shall be the lesser of $8h$ and 5 ft. Concentrated loads and openings shall be considered in determining tendon spacing (ACI 318-19 Sec 8.7.2.3/8.7.2.4)
7. In slabs with unbonded tendons minimum of two tendons shall be provided shall be provided in each direction at columns, either passing through or anchored within region bounded by the longitudinal reinforcement of the column. Outside column and shear cap faces, these two structural integrity tendons shall pass under any orthogonal tendons in adjacent span. Where the two structural integrity tendons are anchored within the region bounded by the longitudinal reinforcement of the column, the anchorage shall be located beyond the column centroid and away from the anchored span. (ACI 318-19 Sec 8.7.5.6.1)
8. Specify on plans:
 - a) The minimum concrete strength at the time of initial prestress. (ACI 318-19 Sec 25.9.4.5.4)

As a covered entity under Title II of the Americans with Disabilities Act, the City of Los Angeles does not discriminate on the basis of disability and, upon request, will provide reasonable accommodation to ensure equal access to its programs, services and activities.

- b) Permissible stresses in concrete at service loads after loss. (ACI 318-19 Sec 24.5.2.2)
 - c) Effective stress in pre-stressing tendon jacking forces, initial anchorage forces and calculated elongations. (ACI 318-19 Sec 20.3.2.5.1)
 - d) The magnitude and location of prestressing forces. (LABC 91.1901.5, #5)
 - e) Stressing sequence for post tensioning tendons. (LABC 91.1901.5, #10)
9. Prestressing, where used for flexural members of special moment frame, shall satisfy (a) through (d):
- a) The average prestress, f_{pc} calculated for an area equal to the smallest cross-sectional dimension of the member multiplied by the perpendicular cross-sectional dimension shall not exceed the smaller of 500 psi and $f'_c/10$.
 - b) Prestressing steel shall be unbonded in potential plastic hinge regions, and the calculated strains in prestressing steel under the design displacement shall be less than 1 percent.
 - c) Prestressing steel shall not contribute to more than one-quarter of the positive or negative flexural strength at the critical section in a plastic hinge region and shall be anchored at or beyond the exterior face of the joint.
 - d) Anchorages of the post-tensioning tendons resisting earthquake-induced forces shall be capable of allowing tendons to withstand 50 cycles of loading, bounded by 40 and 85 percent of the specified tensile strength of the prestress steel. (ACI 318-19 Sec 18.6.3.5)

B. CALCULATIONS

1. Provide design calculations which consider the effects of creep shrinkage and elastic shortening on rigidly connected elements. (ACI 318-19 Sec 4.12.2.2)
2. Provide minimum bonded reinforcement for all flexural members with unbonded tendons as required by ACI 318-19. (ACI 318-19 Sec 8.6.2.3)
3. Provide minimum bonded reinforcement for all P/T two-way flat plates with tensile stress in concrete at service load exceeding $2\sqrt{f'_c}$. (ACI 318-19 sec 8.6.2.3)
4. Computer Solutions show P/T beams and/or slabs with stresses in excess of that allowed for serviceability requirements. Provide design which shows conformity with serviceability requirement for flexural members at right after prestress transfer and at service loads per ACI 318-19, Sec 24.5.3.1, and 24.5.4.1.
5. Should be designed for special seismic load combinations due to the irregularity (ASCE 7-16 12.3.3, Table 12.3-1).
6. The resulting forces and moments induced by $P\Delta$ shall be considered in the design in accordance with ASCE 7-16 Sec 12.8.7. The base shear used to determine the story shears and the story drifts shall be determined in accordance with ASCE 7-16 Sec 12.8.6. (ASCE 7-16 Sec 12.9.6)
7. In structures assigned to seismic design category D,E, or F, horizontal cantilever structural components shall be designed for a minimum net upward force of 0.2 times the Dead load in addition to the applicable load combinations of ASCE 7-16 Sec 12.4 (ASCE 7-16 sec 12.4.4)
8. Except for walls, members with average prestress f_{pc} (due to effective prestress force only) equal to or greater than 225 psi (1.55 MPa) shall have all pre-stressing tendons enclosed by spirals or lateral ties per ACI 318-19, Section 10.7.6.1.3.
9. Pre-stressing force shall be determined per ACI 318-19, Section 26.10.2(e).
10. Provide minimum shear reinforcement for all prestressed and non-prestressed reinforced concrete flexural members where V_u exceed $0.5 V_c$ per ACI 318-19, Section 7.6.3.1
11. Provide calculation for prestressed beam subject to torsion. (ACI 318-19, Sec 9.5.4.4)
12. Provide calculation to show total amount of prestressed and non-prestressed in members with bonded prestressed reinforcement shall be adequate to develop a factored load at least 1.2 times the cracking load per ACI 318-19, Sec 9.6.2.1.

C. NOTES ON PLANS

1. Provide note on plan stating that power driven steel anchors shall not be used in prestressed or post-tensioned concrete members. (LA Information Bulletin: IB P/BC 2020-015)

ADDITIONAL CORRECTIONS	Code section No.